



MILBANK
ENERGY AT WORK

MPRVD-100-MB-78



Catalog Number	MPRVD-100-MB-78
Marketing Product Description	4 Terminal Ring Type 78x8.97x8.16 Plain Top 2-100 Ampere Main Breaker Double Pedestal Direct Bury
UPC	784572237780
Length (IN)	13.603
Width (IN)	8.16
Height (IN)	78
Brand Name	Milbank
Type	Ring Type Meter Socket
Application	Mobile Home Power
Standard	UL Listed;Type 3R
Voltage Rating	Up to 240 Volts Alternating Current
Amperage Rating	100 Continuous Ampere
Phase	1 Phase
Frequency Rating	60 Hertz
Size	13.603L x 8.16W x78H
Number Of Cutouts	2
Cutout Size	Two 100 Ampere Main Breakers
Cable Entry	Underground
Terminal	Double Mechanical
Insulation	Fiberglass with Resin

Mounting	Pedestal
Enclosure	G90 Galvanized Steel with Powder Coat Finish
Jaw Quantity	4 Terminal
Bypass Type	No Bypass
Number of Meter Positions	2 Positions
Equipment Ground	Ground Bar
Hub Opening	Plain Top
Line Side Wire Range	6 AWG - 350 kcmil
Load Side Wire Range	6 - 2/0 AWG
Number Branch Circuits	12
Number Of Receptacles	0

Please consult serving utility for their requirements prior to ordering or installing, as specifications and approvals vary by utility and may require local electrical inspector approval. All installations must be installed by a licensed electrician and must comply with all national and local codes, laws and regulations. Milbank reserves the right to make changes in specifications and features shown without notice or obligation.